



# Tony Sanchez Ltd.



Sales / Service Of Heavy Duty Truck Equipment  
 1685 U.S. Rt. 46  
 Ledgewood, New Jersey 07852  
 973-398-3398  
 Fax 973-328-3607

March 18 2026

County of Passaic  
 1310 Route 23 North  
 Wayne, NJ 07470  
 ESCNJ Bid Number #23/24-04 Class 4 - 8 Trucks  
 Bergen County COOP

2027 Hook Loader, And Associated Equipment  
 This Package is available thru the ESCNJ COOP

Ampliroll A1120116-Hook Loader: ... (CA150) .....Included

- Lifting Capacity 26,000 Lb
- 12-17 Ft Containers
- Dual Arm Cylinders
- 54" or 62" Hook Adjustable
- Installed On Truck Chassis
- Poly Fenders
- \*Power Tarp w/ Power gantry and HD Side Arms

Safety Lighting: .....Included

- \*6 Yellow L.E.D. Oval Strobes
- 4 In front Grill and 2 Mounted In ICC Bar
- 36In LED Light Bar Roof Mounted
- 2 Red L.E.D. Oval Stop-Turn Tail, ICC Bar in Each Side
- Snow Plow Lights-Dual Beam All Weather Low Profile
- \*LED Heated Snow Plow Lights-Dual Beam All Weather Low Profile
- Plow Light Hood Mounting, Back Up Warning System
- 2 Salt Spreader Flood Light, Ice Lights And Reflective Tape
- \*Back Camera

Hydraulic System: .....Included

- Pto & Direct Mount Pump Axial Piston -5,700 Psi 15 Gpm @ 1,500 (Rpm) Sae B,
- 35 Gallon Ss Tank And Valve Enclosure
- Air Control Operated Hook Loader & Plow
- SS Hydraulic Tank & Valve Enclosure
- Electronic Spreader Control , Prewtting

Diamond Aluminum Tool Box: .....Included

- Saddle Mounted
- 36"x 24" x24"

Front Hitch: .....Included

- Hitch Will Be A Front Frame Low Profile Type Design.
- Hitch Will Have 5/8" Thick Custom Built Side Plates
- QCP Receiver

Pintle Hook 25 Ton & H.D. D Rings: .....Included

- ICC Bar - Led Stop / Turn / Tail Lights Mounted In ICC Step
- Ice Lights And Reflective Tape

Estimated Complete / Total Up fit .....\$116,743.00

Gled hill H.D. Snow Plow..... Estimated \$16,500.00

- 11 Foot Straight Steel Snow Plow,
- Height Is 42", Full Trip Assemble
- Tube Table With Power Reversing Assembly,
- Painted Acrylic Enamel 1 Color
- Quick Disconnecting System 1,
- Cove Cut Both Sides
- Curb Shoe ,
- Cushlon Valve
- 36" Unbreakable Markers,
- 3/8x12 Belt Deflector Flap
- Level Lift Chain Kit
- Saber Carbide Cutting Edge,

Buyers V-Box Spreader & Flat Bed..... Estimated..\$49,730.00

- 14' Long x 60" Tall { 10-12 Yards },
- Dual 7" Augers
- Hopper 82" Wide, Side Slope 45 Degrees
- 304 Stainless Steel (Ss) Constructions, 10 Ga 304 Ss Side And Ends
- 12 Ga 304 Ss Inverted V
- 7 Ga 304 Ss Long Sill.
- Carbon Steel Top Screens,
- Swing Up Chute
- 22" Direct Stainless Steel Assembly
- Hydraulic Drive,
- Stainless Steel Safety LED Light Bar
- Dump Gate In Chute
- Prewetting Dual 190 Gal. Poly Tanks Electric Driven
- Flat Bed with a Stainless Steel deck

Respectfully submitted,

*Tony Sanchez Jr.*

Sales Representative

Cell. # 973-296-0092

[tsjr@tsanchez2ltd.com](mailto:tsjr@tsanchez2ltd.com)

Estimated Complete Package.....\$182,973.00

\*Please Note: Due to the unstable prices of steel, this extract prices can only be held for 30 days .  
The attached quote MAY BE subject to a US tariff of 10% to 25%.  
Unfortunately we are currently not able to specify the final tariff amount if any. Further details will available over the next few weeks . If there are any tariffs, they will be applied at the time of delivery . Any prices that are quote are NOT firm and are for estimated budgeting purposing only. We are sorry for any inconveniences this may create.